


ROUTE 3, 14 & MAIN STREET IMPROVEMENT PROJECT



ADDITIONAL TURN LANES

After the project, Main Street will have dual left and dual right turn lanes onto Route 3/14. Route 3/14 traffic will have a dedicated left turn lane, and a shared left, through, and right turn lane.

REDUCE CONGESTION

The \$1.5 million project seeks to reduce congestion and driver delays at the intersection by expanding turn lane capacity.



NEW TRAFFIC SIGNALS

New traffic signal equipment will be installed at the intersection as part of the project to accommodate the additional turn lanes.

NEW PEDESTRIAN FEATURES

New sidewalks with handicapped-accessible ramps, crosswalks, and traffic signal equipment for pedestrian crossings will be installed at the intersection.



CONSTRUCTION CALENDAR

Construction will begin after the Labor Day holiday, on Wednesday, Sept. 9. In December, crews are expected to begin installation of the new traffic signal equipment. All work is expected to be complete in February 2021.

WHAT CAN DRIVERS EXPECT

Most lane closures for construction will be scheduled to occur outside of peak travel times. Outside of restricted hours, motorists are encouraged to allow additional travel time to navigate the work zone area.



STAY INFORMED

For additional information and construction updates, you can visit the project page at www.VirginiaDOT.org. You can also find us on Twitter, Facebook and Nextdoor.